



No NEIGR/ENGG/110/2022/

Dated the 7<sup>th</sup> December, 2022

### NOTICE INVITING QUOTATION

On behalf of the Institute, Sealed quotations for Construction of **Construction of Granite Slab in Microbiology Lab etc** are invited from registered contractors for the following work upto **14<sup>th</sup> December, 2022 by 2:00 P M** and the same will be opened on the same date and time as per details below:

| SI No | Name of work   | Estimated cost | E M D      |
|-------|--|----------------|------------|
| 1     | Construction of Granite Slab in Microbiology Lab etc | Rs.1,17,500/-  | Rs.2,350/- |

#### Terms and conditions:

1. NEIGRIHMS reserves the right to accept or reject any or all quotation without assigning any reason thereof.
2. If the contractor fails to complete the execution and completion of the works as specified in the letter of award and if extension of time is not granted, if any, the contractor shall be bound to pay a liquidated damages a sum of 0.5% (percent) per week of delay for such default subject to a maximum of 5% of the contract price.
3. The quotation should be submitted in a sealed cover and superscripted with the name of work addressed to the Executive Engineer (Civil), NEIGRIHMS
4. The rate should be inclusive of all taxes and duties.
5. Performance Security @ 3% if applicable will have to be submitted by the lowest quotationer.
6. The variation in quantity may be within +/- 15% of the quantity.

Interested bidders may submit their quotations as per the price bid format at Annexure - I at the Office of the Undersigned upto **1400 hrs on 14<sup>th</sup> December, 2022**

Executive Engineer (C)  
NEIGRIHMS

Copy to: 1. Notice Board  
2. Office file

Name of the Work: - Construction of Granite Slab in Microbiology Lab etc

| Sl No | Description  | Unit | Quantity | Rate |
|-------|--|------|----------|------|
| 1     | Providing polished granite tiles of approved quality, size, shape and thickness not less than 18 mm on floors, skirting, risers and treads of steps over 15 mm thick base of cement mortar in prop. 1:3 (1 cement : 3 coarse sand ) including cutting where necessary finished with flush pointing with Fix-A-Tile (Choksey/ Sika/ Pidilite/ Rouf) / white cement slurry mixed with approved pigment to match shade of tiles, mixed with approved pigment to match the shade of the tiles, complete at all levels as specified and directed. (Cement plastering to be measured and paid separately) (Coloured pigment should be in conformity with colour of tiles and as approved and directed by the Department) | Sqm  | 8.13     |      |
| 2     | Steel work riveted and/ or bolted/ riveted in built up sections, frame work including cutting, hoisting, fixing in position and applying a priming coat of red- lead paint up to 4.6m height above plinth including drilling holes, supplying, fitting and fixing with bolts and nuts or welding, if necessary as directed<br><br>(b) In single stanchions (columns) composed of R.S.J. or channels with caps, bases, splices, angle brackets etc  | Qntl | 6.00     |      |
| 3     | Painting two coats (excluding priming coat) on new steel and other metal surface with enamel paint of approved brand and manufacture(Asian paint/ Berger paint/ ICI paint/ J & N paint/ Nerolac) to give an even shade including cleaning the surface of all dirt, dust and other foreign matter<br><br>(a) Surfaces over 100mm in width or girth. (i) General purpose (Asian paint/ Berger paint/ ICI paint/ J & N paint/ Nerolac)  | Sqm  | 19.02    |      |

Signature of Contractor