



No NEIGR/ENGG/102/2022

Dated: - 7th December, 2022

NOTICE INVITING QUOTATION

On behalf of the Institute, Sealed quotations for **Reflective Sign Board from Main Entry Director's Block to Regional Cancer Centre** are invited from registered contractors for the following work upto **14th December, 2022 by 2:00 P M** and the same will be opened on the same date and time as per details below:

SI No	Name of work	Estimated cost	EMD
1	Reflective Sign Board from Main Entry Director's Block to Regional Cancer Centre	Rs.67,893 /-	Rs.1,360/-

Terms and conditions:

1. NEIGRIHMS reserves the right to accept or reject any or all quotation without assigning any reason thereof.
2. If the contractor fails to complete the execution and completion of the works as specified in the letter of award and if extension of time is not granted, if any, the contractor shall be bound to pay a liquidated damages a sum of 0.5% (percent) per week of delay for such default subject to a maximum of 5% of the contract price.
3. The quotation should be submitted in a sealed cover and superscripted with the name of work addressed to the Executive Engineer (Civil), NEIGRIHMS
4. The rate should be inclusive of all taxes and duties.
5. Performance Security @ 3% if applicable will have to be submitted by the lowest quotationer.

Interested bidders may submit their quotations as per the price bid format at Annexure - I at the Office of the Undersigned upto **1400 hrs on 14th December, 2022**

Executive Engineer (C)
NEIGRIHMS

Copy to: 1. Notice Board
2. Office file

Name of the Work: - Reflective Sign Board from Main Entry Director's Block to Regional Cancer Centre

SI No	Description	Unit	Quantity	Rate
1	Earthwork in excavation upto a depth of 2m below the existing ground level for foundation trenches of foundations, footings of column/ walls, retaining walls, septic tank etc. including bailing out water where necessary and removal of surplus earth with all lead and lifts as directed and specified for the following classification of soils (c) In soft or laminated rock or medium shale	Cum	0.61	
2	Providing brick soling in foundation and under floor with stone/ best quality picked jhama brick, sand packed and laid to level and in panel after preparing the subgrade as directed including all labour and materials and if necessary dewatering, complete. (c) Stone soling of thickness 100mm.	Sqm	1.01	
3	Providing form work of ordinary timber planking of thickness not less than 25mm and removal of the same for concrete members so as to give a rough finish including centering, shuttering, strutting and propping etc., for height of propping and centering of supporting floor to the soffit of the concrete member not exceeding 4.0M as specified for the following items: (a) Foundation, footings, bases of columns, pile cap, raft and mass concrete works etc.	Sqm	5.40	
4	Plain cement concrete works with coarse aggregate of sizes 13mm to 32mm in foundation bed for footing steps, walls, brick works etc. as directed and specified including dewatering if necessary, and curing complete (shuttering where necessary shall be measured and paid separately) (a) In prop. 1:3: 6 (1 cement:3 coarse sand :6 coarse agg. by volume (using mixture machine)	Cum	0.61	
5	15 mm thick Cement plaster in single coat on rough side of single or half brick wall for interior plastering up to 1st floor level including arises, internal rounded angles, not exceeding 80mm girth and finished even and smooth including curing complete as directed a) In cement mortar 1:3	Sqm	1.91	
6	Direction and Place Identification Signs with size more than 0.9 sqm size board. A.Retro-reflectorised Traffic Signs (2) Supported on GI pipe 50 mm dia Providing and fixing of retro-reflectorised cautionary, mandatory and informatory sign as per IRC: 67 made of encapsulated lens type reflective sheeting vide clause 1701.2.3 fixed over Aluminium Sheeting 2 mm thick supported on GI Pipe 50 mm dia firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawing and Technical Specification Clause 1701.	Sqm	6.92	

Signature of Contractor