



No NEIGR/ENGG/108/2022/

Dated the 23rd November, 2022

NOTICE INVITING QUOTATION

On behalf of the Institute, Sealed quotations for Construction of **Civil and Plumbing works in CHC Bhoirybong** are invited from registered contractors for the following work upto **7th December, 2022** by **2:00 P M** and the same will be opened on the same date and time as per details below:

SI No	Name of work	Estimated cost	E M D
1	Civil and Plumbing works in CHC Bhoirybong	Rs.55,962/-	Rs.1,120/-

Terms and conditions:

1. NEIGRIHMS reserves the right to accept or reject any or all quotation without assigning any reason thereof.
2. If the contractor fails to complete the execution and completion of the works as specified in the letter of award and if extension of time is not granted, if any, the contractor shall be bound to pay a liquidated damages a sum of 0.5% (percent) per week of delay for such default subject to a maximum of 5% of the contract price.
3. The quotation should be submitted in a sealed cover and superscripted with the name of work addressed to the Executive Engineer (Civil), NEIGRIHMS
4. The rate should be inclusive of all taxes and duties.
5. Performance Security @ 3% if applicable will have to be submitted by the lowest quotationer.
6. The variation in quantity may be within +/- 15% of the quantity.

Interested bidders may submit their quotations as per the price bid format at Annexure - I at the Office of the Undersigned upto **1400 hrs on 7th December, 2022**

Executive Engineer (C)
NEIGRIHMS

Copy to: 1. Notice Board
2. Office file

Name of the Work: - Civil and Plumbing works in CHC Bhoiryabong

SI No	Description	Unit	Quantity	Rate	Amount
1	Stone masonry work in retaining wall, wing wall, abutment, foundation, steps, plinth etc. in cement mortar in prop 1:6 with levelling course of 1:6:12 with unsize stone / Mawthup both faces hammer dressed including bonding, providing face stone, through stone and centering including racking of joints, curing and supplying and all carriage of stone as directed (b) Coursed Rubble Masonry (i) In Sub-structure upto Plinth Level	Cum	5.22		
2	Plain cement concrete floor base in prop 1:3:6 laid in alternate bays as specified with coarse aggregate of size 13mm to 32mm including dewatering if necessary, and curing etc. complete (c) 100 mm thick in prop 1:3:6	Sqm	10.44		
3	15 mm thick Cement plaster in single coat on fair side of single or half brick wall for interior plastering up to 1st floor level including arises, internal rounded angles, not exceeding 80mm girth and finished even and smooth including curing complete as directed b) In cement mortar 1:4	Sqm	22.04		
4	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) Pipes, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings i/c fixing the pipe with clamps at 1.00m spacing. This includes jointing of pipes & fittings, with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as direction of Engineer-in-Charge. Concealed work, including cutting chases and making good the wall etc (a) Exposed or in trenches - (iii) 25mm OD	Rm	24.10		
5	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) Pipes, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings i/c fixing the pipe with clamps at 1.00m spacing. This includes jointing of pipes & fittings, with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as direction of Engineer-in-Charge. Concealed work, including cutting chases and making good the wall etc (a) Exposed or in trenches - (ii) 20mm OD	Rm	22.00		
6	Supplying fitting and fixing C.P. bib cock 15mm dia of approved brand directed and specified (G.I. & C.P. pipes will be measured separately) (a) Bib cock short body	Each	2		

Signature of Contractor