



North Eastern Indira Gandhi Regional Institute of Health and Medical Sciences

(An Autonomous Institute, Ministry of Health and Family Welfare, Government of India)

Director's Block, Mawdiangdiang, Shillong 793 018 (Meghalaya)

**Website:** [www.neigrihms.gov.in](http://www.neigrihms.gov.in)

**Tender No: CVENGG-ESTI/144/2025 -Engg (C):**

**Dated 3<sup>rd</sup> February, 2026**

### **TENDER /BID DOCUMENT**

**ONLINE OPEN E- TENDER ARE INVITED FROM REGISTERED CONTRACTORS OF  
PWD/ PHE/ ESTATE OFFICE (GAD)/ MES/ MeECL AND EQUIVALENT CLASS OF  
CPWD FOR REPAIR WORKS IN GENERAL WARD BLOCK WASH AREAS  
(e -Procurement)**

Bid Document Downloading Start Date:	1400 hours of 4.2.2026
Last Date and Time for Submission of Bid Document Online:	1400 hours of 17.2.2026
Last date and Time of Receipt of Earnest Money Deposit (hard copies):	1400 hours of 17.2.2026
Date and Time of Opening of Techno -Commercial Bids:	1400 hours of 18.2.2026
Cost of Earnest Money Deposit (EMD):	Rs.1,54,330/-

Bidders /Tenderers can download the tender /bid document from Central Public Procurement Portal website at [www.eprocure.gov.in](http://www.eprocure.gov.in) Bidders /Tenderers are required to submit their bid online by uploading all the relevant documents through [www.eprocure.gov.in](http://www.eprocure.gov.in)

Tender document can also be downloaded from the Institute's website at [www.neigrihms.gov.in](http://www.neigrihms.gov.in) For further details regarding amendment /addendum /extension please visit website: [www.eprocure.gov.in](http://www.eprocure.gov.in) and [www.neigrihms.gov.in](http://www.neigrihms.gov.in)

In the event of the date being declared as a closed holiday for purchaser's office, the due date for submission of bids online and opening of bids online will be the following working day at the appointed time.

### DETAILED TENDER NOTICE

Online tenders in two bid systems are invited from registered contractors of PWD/PHE/Estate office (GAD)/MES/MeECL and equivalent class of CPWD for the following work.

Name of work	Estimated cost (Rs) (approx)	EMD (Rs)
Repair works in General ward block Wash areas	Rs.77,16,309/-	Rs. 1,54,330/-

#### **General Conditions of Contract (GCC):**

1. Bidders /Tenderers would be required to register on the Central Public Procurement Portal at [www.eprocure.gov.in](http://www.eprocure.gov.in), using a valid Digital Signature Certificate (DSC) and valid email address to be able to participate in the bidding process. On registration with the Portal they will be provided with a user id and password by the system through which they can submit their bids online.
2. Digital Signature Certificate (DSC) may be obtained from any authorized agencies registered with the Certifying Authority (CA), through National Informatics Center (NIC) in India.
3. Bidders /Tenderers can download the bid document from Central Public Procurement Portal website at [www.eprocure.gov.in](http://www.eprocure.gov.in) Bidders /Tenderers are required to submit the tender documents online by scanning and uploading with all the relevant documents through [www.eprocure.gov.in](http://www.eprocure.gov.in)
4. Tender document can also be downloaded from the Institute's website at [www.neigrihms.gov.in](http://www.neigrihms.gov.in) For further details regarding Amendment /Addendum /Extension please visit website: [www.eprocure.gov.in](http://www.eprocure.gov.in) and [www.neigrihms.gov.in](http://www.neigrihms.gov.in)
5. **Earnest Money Deposit (EMD) in the form of Call deposit, Banker's Cheque, Fixed deposit or Demand draft, drawn in favour of NEIGRIHMS EMD Security Deposits** or Bank Guarantee of any Scheduled Bank, shall be scanned and submitted online, along with the Techno-commercial bid (Un priced Bid), within the period of tender online submission date and time and the original (hard copy) should be dropped in the tender box in the Engineering Section, Director's Block, Mawdiangdiang, NEIGRIHMS, Shillong -793018 , **not later than the last date of e-submission of the tender**
6. The technical bids will be opened online by a committee of members duly constituted for the purpose at the time and date as specified in the tender document. All statements, documents, certificates, Affidavits, etc uploaded by the bidders will be verified and downloaded for technical evaluation and the result of technical bid evaluation will be displayed on [www.eprocure.gov.in](http://www.eprocure.gov.in) which can be seen by all bidders who participated in the tender.
7. The bidders should download the **BoQ.xls** from CPP Portal and filled in the blank spaces provided for mentioning the name of bidder and rates. Bidders cannot modify any other text or background shown in the BOQ template or replace it with any other copy of same **BOQ in .xls format**. NEIGRIHMS /Central Public Procurement Portal ([www.eprocure.gov.in](http://www.eprocure.gov.in)) will accept the BOQ template only and hence the rate should not be quoted in any other place except BOQ template.
8. The Financial bid (price bid) i.e. Bill of Quantity (BOQ) of only technically qualified bidders will be opened online by a committee of members and the result will be displayed on the [www.eprocure.gov.in](http://www.eprocure.gov.in) which can be seen by all bidders who participated in the tender.
9. **Contractor shall quote the rate of AT PAR or ABOVE the Meghalaya PWD Schedule of Rates for buildings 2021 – 22 / for Roads 2020 – 21 and as per prevailing market rate for the Non Schedule Items. The Institute will not guarantee allotment of the works to any bidder quoting BELOW PAR.**
10. The site is located at Mawdiangdiang
11. Time of completion: 10 (ten) months from the date of issue of commencement order.
12. Contractors shall be deemed to have inspected and examined the site of work and its surroundings and familiarized themselves, before submitting the tenders.
13. Tenderers will have to submit copy of their registration, which is valid as on the last date of bid submission.
14. The contractor shall not sub-contract the work to sub-contractors or to any single sub-contractor. An undertaking by the contractor shall have to be submitted to this effect.
15. The successful contractor shall provide a performance security for his proper performance of the contract within 7 (seven) days from the date of receipt of letter of award. The performance Security shall be in the form of FD/Call Deposit to be pledged in favour of Deputy Director (Admn), NEIGRIHMS. The amount of the security shall be 5% (five percent) of the contract price. The performance security shall remain valid for a minimum period of sixty days beyond the date of completion of all contractual obligations and shall be returned to the contractor within 14 days after expiry of the performance security. If the contractor fails to perform the work as per terms and conditions of the contract, the performance security shall be forfeited at his own risk and responsibility.
16. If during the execution of the work the contractor encounters physical obstructions or physical conditions other than climatic conditions on the site, which obstructions or conditions were in his reasonable opinion not foreseeable by the contractor, the contractor shall forth with give notice thereof to the Superintending Engineer NEIGRIHMS. On receipt of such notice, the Superintending Engineer shall, in his opinion feel that such obstructions/conditions could not have been reasonably foreseen by the contractor, after due consultation with the contractor determine any extension of time with no financial bearing to which the contractor is entitled.

17. During the execution of the works, the contractor shall keep the site reasonably free from all unnecessary obstructions and shall store or depose of any contractors equipment and surplus materials and clear from the site any wreckage, rubbish or temporary works in consultation with the Sanitary Supt of the Institute.
18. Before issue of any completion certificate, the contractor shall clear away and remove from that part of the site to which the completion certificate relates all contractors' equipment, surplus material, rubbish and temporary works of every kind.
19. The contractor while employing labour should ensure that all the statutory labour laws and regulations are adhered to.
20. In the event of
  - a. The amount or nature of extra or additional work
  - b. Exceptionally adverse climatic conditions
  - c. Other special circumstances which may occur other than through a default or breach of contract by the contractor or for which he is responsible. Being such as fairly to entitle the contractor to extension of time for completion of the works or any section or part thereof, the Institute shall after due consultation with the contractor and subject to clause 16 determine the amount of such extension with no financial bearing and shall notify the contractor accordingly.
21. If the contractor fails to complete the execution and completion of the works as specified in the work order, the contractor shall be bound to pay as liquidated Damages a sum of 0.5 % (percent) per week of delay for such default subject to a maximum of 5 % of the contract price.
22. When whole of the works have been substantially completed, the contractor shall give a notice to the Superintending Engineer of the Institute, accompanied by a written undertaking to finish with due expedition any outstanding work during the defect Liability period. Such notice and undertaking shall be deemed to be a request by the contractor to the Superintending Engineer to issue a taking over certificate.
23. Defect liability period shall be 12 (twelve) months calculated from the date of completion of the works certified by the Superintending Engineer in the completion certificate.
24. If the contractor fails to fulfill any of the obligations under this contract, the Institute shall be at liberty to terminate the contract thereby voiding the contract and will be at liberty to allot the whole work or balance works to any other party at the risk and cost of the first party.
25. All works are to be carried out as per current specification prevailing in the state of Meghalaya (MPWD & CPWD) and when directed by the Institute.
26. Bidders are to note that since the Institute adopts the Scheduled of Rates of Meghalaya State and since Meghalaya State don't allowed price escalations, so also the Institute will not entertain any price escalation.
27. **Average Annual Financial Turnover** during the last five years ending 31<sup>st</sup> March of the previous financial year should be at least **30 % of the estimated cost**. Tenderer to submit Financial Statement from Chartered Accountant as per **FORMAT – B**.
28. Parties should have the experience of having successfully completed similar works during the last 5 (five) years ending last day of month previous to the one in which applications are invited should be either of the following: (a). **Three similar completed works each** costing not less than the amount equal to **40% of the estimated cost** or (b) **Two similar completed works each** costing not less than the amount equal to **50 % of the estimated cost** or (c) **one similar completed work** costing not less than the amount equal to **80 % of the estimated cost**. Documentary proof in the form of completion certificates only are to be enclosed failing which the tender will be non-responsive.
29. Completion Certificates should indicate the items of works executed along with the date of award of work & time of completion as per work order & actual time of completion and are to be signed by Officers not below the rank of Executive Engineers or Equivalent (**FORMAT –A**)
30. **AVAILABLE BID CAPACITY**  
 Applicants who meet the minimum qualification criteria will be qualified only if their available bid capacity at the expected time of bidding is more than the total estimated cost of the work. The available bid capacity will be calculated as under:  
**Available Bid Capacity = (A x N x 2 – B)**, where:  
 A - Maximum value of works executed in any one year during the last five years (updated to the current price level). Rate of inflation may be taken as 10% per year which will take into account the completed as well as works in progress  
 B – Value of work at current price level of the existing commitment and outgoing work to be completed during the next 15 months (period of completion of work for which are invited)  
 N – Number of years prescribe for completion of the works for which the bid are invited is the number of years prescribed for completing the works
31. **FINANCIAL CRITERIA / Bank Credit certificate**
  1. The applicant shall demonstrate that he/she has access to or has available, liquid assets (working capital and cash in hand) and/or credit facilities of not less than 40% of the contract applied for.
  2. **Bank Credit certificate** (in original) @ 40% of Value of the work in Banker's letter head (not more than three months old) and relevant documents shall be enclosed with the tender documents to prove the applicant's financial capacity and credit credential.
32. Running payments can be made to the contractor subject to certification by the Superintending Engineer after completion of about 50 % of the work and final payment will be paid after completion of the work after due certification and satisfaction of the Superintending Engineer.
33. Parties to submit PAN Card, GST Registration, valid Labour License from Labour Department

34. Rates once accepted will not be enhanced due to variation in the rate of materials, labour and Government taxes.
35. Bidder should submit documents showing that they have enough plant and machineries. Undertaking in the form of affidavit to be submitted. No tools and plants will be supplied by the Institute
36. No materials will be supplied by the Institute.
37. The quoted rates shall be firm, fixed and binding on the contractor irrespective of any variation in the quantities stated in the contract upto  $\pm 15\%$  variation of the contract value as a whole.
38. Successful Non –Tribal tenderers should submit the valid Trading license within 14 (fourteen) days from the date of issue of preliminary work order, failing which the order shall be withdrawn at their risk and responsibility. Trading License submitted should be specifically for similar nature of work for which the tender is called for.
39. **In case of dispute:** It is agreed between the first party and the second party that all disputes, differences and claims whatsoever which shall arise at any time between the parties hereto or their respective representatives concerning this contract and all other documents in pursuance hereof as to the rights, duties, obligations or liabilities of the parties hereto respectively by virtue of this contract shall be referred to Arbitration in accordance with the provisions of the Arbitration and Conciliation Act, 1996 as amended from time to time. Either party may refer the matter of Arbitration to the sole arbitrator to be appointed by the First party. The arbitrator so appointed shall be a neutral third party whose decision shall be binding and accepted by both the parties.
40. The specifications and mode of measurement for civil works shall be in accordance with PWD/CPWD specifications unless otherwise specified and more specifically as per approved Drawing, Specification and Estimate.
41. In the event of responsive parties quoting same rates, the **Institute reserves the right to allot the work to the bidder having higher / highest credentials in terms of similar work experience, etc.**
42. If there is any excess payment on any item etc made to the contractor, the contractor shall not hesitate to cooperate in adjusting / deducting the same from either the running bills or final bills.
43. The Institute reserves the right to accept or reject any or all tenders without assigning any reason thereof
44. All the above requirements are compulsory for fulfillment as part of the tenders failing which tenders will be rejected.
45. All documents, registrations should be valid as on the last date of tender.
46. Taxes as applicable will be deducted from the bills of the contractor.
47. Parties to submit the list of technical staff with at least one experienced Junior Engineer-Civil (Diploma). Attested copy of diploma/degree certificates to be enclosed. Undertaking in the form of affidavit to be submitted.
48. The parties to furnish an affidavit on a non-judicial stamp paper that there is no police/vigilance/CBI case pending against them.
49. Successful bidder will have to furnish an Undertaking to carry out/ execute the work in strict conformity to the specifications as mentioned in the scheduled items and guide notes of the Scheduled of Rates and Indian Standard codes of practice for materials / as per direction of the Engineer-in-charge failing which he/she shall be liable for disqualification/ blacklisted from participating in future tenders of NEIGRIHMS
50. The Party shall be responsible for the safety of all its workmen/employees during the period of execution of the work. The party shall provide all safety materials, gadgets, equipments etc to all its workmen/employees to ensure their safety during execution of the work. The Institute shall not be held responsible in case of any accidents, mishaps etc to the party and its employees
51. Any delay in completion of the works beyond the stipulated date due to reasons attributable to the contractor may eventually lead to cancellation of letter of award for which the contractor is not entitled to any compensation. The cancellation of letter of award would lead to forfeiture of performance security.
52. The contractor is to register with the Labour Department for the work and the registration certificate has to be submitted, failing which the bill cannot be processed
53. If any statutory tax/deduction/recovery is notified by the State/Central Govt, the same shall be deducted from the bill of the contractors as applicable from its effective date of coming into force.
54. The Payment for the work done by the Contractor will be on the basis of measurement of the work executed. The Contractor or his authorized agent or representative shall be present at the time of recording of each set of measurements and sign on the measurement book as a token of acceptance of the measurement.
55. Contractors who engage / employ five or more Inter State Migrant Workmen is required to obtain a license from District Labour Office, East Khasi Hills, Shillong as per prevailing labour laws applicable in the State.
56. Bidders should note that the above terms and conditions will apply specifically in addition to the rules / regulations applicable to works in the Government of India.
57. All rules of GFR will be applicable
58. Wherever relevant, water charges @ 1% on the Order value will be as applicable
59. Electricity charges when used by the Contractor will be deducted from the bill as per actual usage/consumption through tested meter in consultation with Electrical Department of the Institute.
60. Forest Royalty of stone and sand shall be deducted as per latest rate of Forest Department Government of Meghalaya

Sd/  
Superintending Engineer  
NEIGRIHMS

**Check List of documents to be submitted along with the tender:**

<b>Sl No</b>	<b>Documents</b>	<b>Remarks</b>
1	Tender documents	
2	Earnest money Deposit	
3	Copy of registration	
4	Undertaking not to sub-let the work. (format enclosed with the tender)	
5	Pan Card.	
6	G S T certificate	
7	Valid Labour License	
8	Documentary proof of work orders, completion certificates as specified in clause 28 of the GCC.	
9	Completion certificates as per FORMAT – A	
10	Average Annual Financial Turnover during the last five years as per FORMAT - B	
11	List of technical staff with Undertaking in the form of affidavit (Degree/Diploma certificate to be enclosed)	
12	Affidavit of no vigilance/police/CBI case pending against them	
13	Plant and machineries. Undertaking in the form of affidavit	
14	FINANCIAL / Bank Credit certificate	

### **FORM OF UNDERTAKING**

To

The Superintending Engineer  
NEIGRIHMS

Sub: Repair works in General ward block Wash areas

Sir,

With reference to the above, I hereby undertake not to sublet the work cited above, if the work is allotted to me.

Date:

*Name of contractor	
*Full postal Address	
*Email Address	
*Mobile No	
*Alternate Mobile No	
*Signature and Seal	

All the fields marked \* above are mandatory to be furnished by the contractor

**FORMAT - A.**

1. Name of Contractor: - .....
2. Name of work completed: - .....
3. Agreement No: - .....
4. Name of Division in which work was executed: - .....
5. Tender Cost: - .....
6. Stipulated date of Start (as per w/o):- .....
7. Stipulated date of Completion (as per w/o):- .....
8. Actual date of Completion: - .....

Signature of Contractor

\*\*Signature of Officer issuing the C/Certificate

\*\* (Officer should not be lower than the rank of Executive Engineer – Civil)

**FORMAT B**

**FINANCIAL STATEMENT**

<b>SL NO</b>	<b>FINANCIAL PERIOD</b>	<b>AMOUNTS IN LAKHS</b>
<b>1.</b>	<b>2020 – 2021</b>	
<b>2.</b>	<b>2021 - 2022</b>	
<b>3.</b>	<b>2022 - 2023</b>	
<b>4.</b>	<b>2023 - 2024</b>	
<b>5.</b>	<b>2024 - 2025</b>	

SIGNATURE OF  
CONTRACTOR

SIGNATURE OF  
CHARTERED ACCOUNTANT



I, Shri \_\_\_\_\_, son of Shri \_\_\_\_\_,  
aged about \_\_\_\_\_, resident of  
\_\_\_\_\_  
\_\_\_\_\_ do hereby solemnly affirm and declare on oath as follows:-

- DEPONENT

Identified by:

(Advocate, Shillong)

## Bill of Quantity

Name of the Work: - Repair works in General ward block Wash areas

SI No	Description	Unit	Quantity
1	Demolishing cement concrete including disposal of material within 50 metres lead as per direction of Engineer-in-charge a) Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	Cum	27.25
2	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	Sqm	528.00
3	Demolishing brick work including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.	Cum	1.75
4	Dismantling cement asbestos ceiling/ hard board ceiling/ any type ceiling or partition walls including stacking of serviceable materials and disposal of unserviceable materials within 50 metres lead	Sqm	252.50
5	Taking out doors, windows and clerestory window shutters (steel or wood) including stacking within 50 metres lead: b) Of area beyond 3 sqm	Sqm	79.50
6	Dismantling W.C. Pan of all sizes including disposal of dismantled materials i/c debris all complete as per directions of Engineer-in-Charge	Each	35
7	Providing and laying cement concrete in retaining walls etc and all works above plinth level such as pilasters, columns, pillars, posts, struts, buttresses, parapets, coping, plain window sills, fillets, sunken floor etc., up to first floor level, excluding the cost of centering, shuttering and finishing c) 1:1½:3 (1 cement: 1½ coarse sand: 3 graded stone aggregate 20 mm nominal size).	Cum	13.6
8	Cement concrete floor topping 1:1:2 (1 cement: 1 coarse sand: 2 stone aggregate) finished with a floating coat of neat cement, including cement slurry, complete. b) 20 mm thick	Sqm	90.75
9	15 mm cement plaster on the rough side of single or half brick wall of mix: a) 1:4 (1 cement: 4 fine sand)	Sqm	528.00
10	Providing and fixing 1st quality ceramic glazed floor tiles conforming to IS:15622 (thickness to be specified by the manufacturer) of approved make in all colours and shades of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kg/sqm including pointing in white cement mixed with pigment of matching shade complete	Sqm	90.75
11	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS:15622 (thickness to be specified by the manufacturer), of approved make, in all colours and shades of any size as approved by Engineer-in-Charge, in walls, skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete. a) Normal range	Sqm	528.00
12	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS:733 and IS:1285, fixing with dash fasteners of required diameter and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing/ panelling, C.P. brass/ stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, and panelling to be paid for separately): a) For fixed portion (iii) Polyester powder coated aluminium (minimum thickness of polyester powder coating 50 micron)	Kg	382.50
13	Providing and fixing ISI marked flush door shutters conforming to IS:2202 (Part I) decorative type, core of block board construction with frame of 1st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters. a) 35 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	Sqm	92.70
14	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS:1868) transparent or dyed to required colour or shade, with necessary screws etc. complete: b) 250x10 mm	Each	50

15	Providing and fixing bright finished brass handles with screws etc. complete: a) 125 mm	Each	100
16	Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS:1868) transparent or dyed to required colour and shade, with necessary screws etc. complete. b) Twin rubber stopper	Each	5
17	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS:1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete: a) 300x16 mm	Each	50
18	Surface Preparation: a) Removing existing white or colour wash on wall surfaces by steel wire brushing and/ or scraping, sand papering and preparing the surface smooth including necessary repairs to scratches complete.	Sqm	278.00
19	Providing and applying Plaster of Paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete.	Sqm	92.65
20	Applying one coat of water thinnable cement primer of approved brand and manufacture on surfaces: Water thinnable cement primer	Sqm	278.00
21	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade: Old work (one or more coats)	Sqm	556.00
22	Providing and installing false ceiling at all heights including providing and fixing of frame work with 9 mm thick Gypsum tile with prelude grid complete as per directions of Engineer-in-Charge	Sqm	252.50
23	Providing and fixing wash basin with C.I. brackets, 15 mm dia. CP Brass single hole basin mixer of approved quality and make, including painting of fittings and brackets, cutting and making good the walls wherever required:- White Vitreous China Wash basin size 550x400 mm with a 15 mm CP Brass single hole basin mixer	Each	5
24	Providing and fixing white vitreous china pedestal for wash basin completely recessed at the back for the reception of pipes and fittings	Each	5
25	Providing and fixing PTMT Waste Coupling for wash basin and sink, of approved quality and colour	Each	5
26	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 a) 15mm nominal bore	Each	60
29	Providing and fixing unplasticised P.V.C. connection pipe with PTMT Nuts, collar and bush of approved quality and colour b) 15 mm nominal bore with 45 cm length	Each	40
30	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. b) Flexible pipe 32 mm dia. and 40mm dia.	Each	5
31	Providing and fixing C.P. brass long nose bib cock of approved quality conforming to IS standards and weighing not less than 810 gms. a) 15 mm nominal bore	Each	75
32	Providing and fixing PTMT towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour b) 600mm	Each	25
33	Providing and fixing PTMT grating of approved quality and colour. a Circular type (ii) 125 mm nominal diameter with 25 mm waste hole	Each	20
34	Providing and fixing PTMT soap Dish Holder having length of 138mm, breadth 102mm, height of 75mm with concealed fitting arrangements, weighing not less than 106 gms	Each	30
35	Providing and fixing C.P. brass shower rose with 15 or 20 mm inlet: b) 150 mm diameter	Each	15
36	Providing and fixing CP Brass Single lever telephonic wall mixer of quality & make as approved by Engineer-in-charge	Each	15

37	Providing and fixing toilet paper holder: C.P. brass	Each	35
38	Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6 mm thick hard board backing: b) Rectangular shape 453x357 mm	Each	15
39	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS:7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required: a) W.C. pan with ISI marked white solid plastic seat and lid	Each	25
40	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm sand Cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS:7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required: a) White Vitreous china Orissa pattern W.C. pan of size 580x440 mm with integral type foot rests	Each	10
41	Supplying, fitting and fixing of 450mm grab bar	Each	10
42	Providing and fixing double scaffolding system (cup lock type) on the exterior side, up to seven story height made with 40 mm dia. M.S. tube 1.5 m centre to centre, horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube chollies, M.S. clamps and M.S. staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it thereafter. The scaffolding system shall be stiffened with bracings, runners, connection with the building etc. wherever required for inspection of work at required locations with essential safety features for the workmen etc. complete as per directions and approval of Engineer-in-charge. The elevational area of the scaffolding shall be measured for payment purpose. The payment will be made once irrespective of duration of scaffolding	Sqm	300.00
43	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc. (iii) 25 mm nominal outer diameter Pipes	Rm	3000.00
44	Supplying, fitting and fixing PVC pipes, fittings etc 160mm	Rm	750.00
45	Loading and unloading of materials from Quarry to Worksite A) Stone	Cum	92.550
46	Loading and unloading of materials from Quarry to Worksite B) River sand	Cum	52.20
47	Loading and unloading of materials from Quarry to Worksite C) Dismantled Materials	Cum	27.25
48	Haulage (Excluding Loading and Unloading) A) Stone: Quarry at 23 Km of Shillong -Sohra road (Av Lead = 36 KM)	tkm	6941.625
49	Haulage (Excluding Loading and Unloading) B) River Sand: Quarry at 21 Km of Shillong - Tamabil road (Av Lead = 27 KM)	tkm	3521.8125
50	Haulage (Excluding Loading and Unloading) C) Dismantled Materials: Dumping ground (say 15 KM away)	tkm	981.00
51	Head Load on Transportation of materials	Percentage	0.15